## HASSAN DIVISION.

*Dated 22nd March* 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 10th April 1916, for extending and improving the A.-V. School, Channarayapatna. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 12 noon and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for extending and improving the A.-V. School at Channarayapatna," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate quantities of work for constructing A.-V. School at Channarayapatna.

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| 1 | Removing the existing roof with tiles, reepers, etc., and stacking | Sq. | 22·00 |
| 2 | Dismantling masonry walls | C. ft. | 1,125 |
| 3 | Sundry items that may be found necessary during dismantling, etc. | Lump | sum. |
| 4 | Earthwork excavating for foundation | C. yd. | 87 |
| 5 | Stone in clay, foundation | C. ft. | 2,626 |
| | Do basement | ,, | 1,079 |
| 6 | Burnt brick in clay superstructure | ,, | 4,859 |
| 6a | Do in mortar do | ,, | 982 |
| 7 | Do archwork | ,, | 113 |
| 8 | Burnt stone slabs, dressed, 4" to 6" thick | S. ft. | 295 |
| 9 | Fixing old slabs | ,, | 151 |
| 10 | Forming caps and bases of pillars in verandah | Each | 8 |
| 11 | Moulding with pillasters around arches, etc. | Lump | sum. |
| 12 | New teakwood panelled doors with fastenings, etc. | S. ft. | 236 |
| 13 | New teakwood windows with iron bars, iron work and glazed shutters, etc. | ,, | 63 |
| 14 | Teakwood circular ventilators with glazed shutters | ,, | 48 |
| 15 | Burnt stone slab pillars nicely dressed and grooves cutting and fixed | ,, | 72 |
| 16 | Removing and refixing old doors and windows | Each | 10 |
| 17 | Teakwood, wrought and put up complete | C. ft. | 267·90 |
| 18 | Refixing old bressummers and rafters to front verandah | Lump | sum. |
| 19 | Stone brackets to support purlins of front verandah | Each | 24 |
| 20 | Roofing with 1st class Mangalore tiles, teak reepers, etc., complete | Sq. | 32·30 |
| 21 | Roofing with old Mangalore tiles, teak reepers, etc., complete | ,, | 22·00 |
| 22 | Ridge tiles set in mortar and pointed | R. ft. | 80 |
| 23 | Resetting old ridge tiles in motar and pointed | ,, | 65 |
| 24 | Providing zinc sheets and planking for valleys and mortar bands | S. ft. | 369 |
| 25 | Teakwood cave board | R. ft. | 356 |
| 26 | Refixing old cave board | ,, | 75 |
| 27 | Teakwood finials | Each | 4 |
| 28 | Do pendants | ,, | 8 |
| 29 | Chunam plastering | Sq. | 104·40 |
| 30 | White and colorwashing | ,, | 104·40 |
| 31 | Flooring with first class Mangalore tiles, 9" square over 3" concrete bed and cement pointing, complete. | ,, | 13·00 |
| 32 | Do with Cuddapah slabs over 3" concrete bed and cement pointing, etc., complete. | ,, | 4·00 |
| 33 | Painting doors and windows | ,, | 22·04 |
| 34 | Chunam borders over roof | R. ft. | 326 |
| 35 | Front pediment work as per plan | Lump | sum. |
| 36 | Repairs to existing building including white and colorwashing and unforeseen items, etc. | Lump | sum. |
| 37 | Clearing site and levelling ground and removing high ground in rear, filling ditch in front and forming play ground, etc. | Lump | sum. |

K. R. SESHACHAR,
*Executive Engineer.*